

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-063-20,871-00-00 (of this well)
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR F & M Oil Co., Inc. OPERATORS LICENSE NO. 5313

ADDRESS 422 Union Center, Wichita, Ks. 67202 PHONE # (316) 262-2636

LEASE (FARM) Kuntz "D" WELL NO. #1 WELL LOCATION 69' SW of C NW NW COUNTY Gove

SEC. 11 TWP. 13S RGE. 27W (E) or (W) TOTAL DEPTH 4440 PLUG BACK TD -----

Check One:

OIL WELL GAS WELL D & A X SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8 SET AT 389 CEMENTED WITH 200 SACKS

CASING SIZE ---- SET AT ----- CEMENTED WITH ----- SACKS

PERFORATED AT N/A

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Set 1st plug @ 2130' w/30 sxs, set 2nd plug @ 1180' w/100 sxs & 1 sx flo-cel, 3rd plug @ 390' w/50 sxs, 4th plug @ 40' w/ solid bridge & 10 sxs, 10 sxs in the rat hole, cmt. by Allied w/50/50 pozmix, 6% gel, 3% CC, plug down @ 4:45 PM 1-13-85
(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Not required IS ACC-1 FILED? Yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN 3:00 p.m. January 13, 1985

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION. RECEIVED
STATE CORPORATION COMMISSION

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS: FEB 13 1985

John Armbruster PHONE # (316) 267-0613 CONSERVATION DIVISION
Wichita, Kansas

ADDRESS 501 Union Center, Wichita, Kansas 67202

PLUGGING CONTRACTOR B & B Drilling, Inc. LICENSE NO. 598

ADDRESS 501 Union Center, Wichita, Ks. 67202 PHONE # (316) 267-0613

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]
(Operator or Agent)

DATE: February 11, 1985