

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Rains & Williamson Oil Company, Inc., & Bill J. Porter,

Complete Address 435 Page Court, Wichita, Kansas.

Lease Name Mendenhall Well No. 1

Location SW-SW-SE Sec. 21 Twp. 13 Rge. (E) (W) 28

County Gove Total Depth 4693'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Rains & Williamson Oil Company, Incorporated,

Address 475 Page Court, Wichita, Kansas. License No.

Operation Completed: Hour 1:00 PM Day 18 Month 9 Year 1972

The above well was plugged as follows:

346'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 900'.

Circulated hole with heavy mud. Pulled DP to 1115' and displaced 110 Cu. Ft. cement
thru DP from 1115' to 790'. Pulled DP to 375' and displaced 30 Cu. Ft. cement thru
DP from 375' to 300'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: H. L. Nichols
Well Plugging Supervisor

INDEXED
9/20/72
INV. 6344-u