

15-063-20093-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Nadel and Gussman,
Complete Address 514 Union Center Building, Wichita, Kansas.
Lease Name Bethel Well No. 1
Location 150' NW of CNW-NE Sec. 1 Twp. 13 Rge. (E) (W) 28
County Gove Total Depth 4395'
Abandoned Oil Well Gas Well Input Well SWD Well D & A I
Other well as hereafter indicated
Plugging Contractor John O. Farmer, Incorporated,
Address Box # 352, Russell, Kansas. License No.
Operation Completed: Hour 4:00 PM Day 22 Month 11 Year 1971

The above well was plugged as follows:

2h2'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 800'.

Circulated hole with heavy mud. Pulled DP to 1025' and displaced 100 Sx. cement thru
DP from 1025' to 700'. Pulled DP to 275' and displaced 25 Sx. cement thru DP from
275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. D. Nichols
Well Plugging Supervisor

DATE 12/1/71
INV. NO. 4749-W