

15-063-00052-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NW NW NW

SEC. 31 TWP. 13 RGE. 28W

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Johnson

Operator B & R Brg Co Address Russell, Kans

Field _____ County Gove

Total Depth 4582 Feet.

(Describe briefly the manner in which the well was plugged)

8 1/2" at 198' circulated with cement - 5 1/2" at 4518' with
100 sax cement behind - Baker plugs at 3844' top perforations
at 3824' - Filled with chat to 3815' set 4 sax cement with dump
bailer, pulled 3170' 5 1/2", filled hole with mud to 198', set rock
and 15 sax cement, mud to 35', set rock and 10 sax cement to
bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUN 9 - 1952
CONSERVATION DIVISION
Wichita, Kansas

District Conservation Agent

Date 8-5-52

PLUGGING
FILE SEC 31 TWP 13 RGE 28W
BOOK PAGE 22 LINE 8