

15-063-20098-00-00

Form CP-3
Rev. 6-4-68

KANSAS

AP

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 23 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center Building, Wichita, Kansas.

Lease Name Evans Well No. 1

Location SW-NW Sec. 30 Twp. 13 Rge. (E) (W) 28

County Gove Total Depth 3850'

Abandoned Oil Well Gas Well Input Well SWD Well D & A I

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 10:30 PM Day 17 Month 12 Year 1971

The above well was plugged as follows:

2 1/4'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 975'.

Circulated hole with heavy mud. Pulled DP to 1200' and displaced 110 Cu. Ft. cement
thru DP. from 1200' to 875'. Pulled DP to 220' and displaced 30 Cu. Ft. cement thru
DP from 220' to 145'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement
to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *W. L. Nichole*
Well Plugging Supervisor

DATE 1-11-72

INV. NO. 4935-W