

Y
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 5 - 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name L. J. Dreiling & Sons, Incorporated,

Complete Address: Victoria, Kansas.

Lease Name Hockersmith Well No. 1

Location NW-NE Sec. 36 Twp. 13 Rge. (E) (W) 29

County Gove Total Depth 4515'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Above

Address: License No.

Operation Completed: Hour 7:00 AM Day 31 Month 1 Year 1968

The Above well was plugged as follows:

157'--8 5/8" Surface casing, cement circulated with 125 Sx.
Dakota section from 875' to 1075'.

Circulated hole with heavy mud. Pulled DP to 1090' and displaced 100 Sx. cement thru
DP from 1090' to 775'. Pulled DP to 180' and displaced 20 Sx. cement thru DP from 180'
to 120'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *M. L. Nichols*
Well Plugging Supervisor

2/5/68
7194-W