

15-063-00050-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 134-43
LOCATION NW NW SE
SEC. 8 TWP. 13 RGE. 30

Dry Hole Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Beougher

Operator Morgenstern & Specter Address Russell, Kans

Field _____ County Gove

Total Depth 4604 Feet.

Plugging Contractor Jim Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____
(Describe briefly the manner in which the well was plugged)

10 3/4" at 105' circulated with cement - 5 1/2" at 4185' with
100 sax cement behind - P.B. to 4090', perforated at 4079'
Filled with sand to 4000', set 4 sax cement with dump bailer,
pulled 900' 5 1/2" - mud to 100', set rock and 22 sax cement,
top of cement at 125' - left as water well for land owner as
per authorization attached.

Edwin Kelly
District Conservation Agent

Date 9-11-55

PLUGGING
FILE SEC 8 TWP 13 RGE 30
BOOK PAGE 134 LINE 43

09-13-1955
CONSERVATION DIVISION
Wichita, Kansas