

15-063-20020-00-00

Form CP-3  
Rev. 6-9-67

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

NOV 29 1967  
11-29-67  
CONSERVATION DIVISION

Operator's Full Name Sun oil Company,  
Complete Address Box #3383, Tulsa, Oklahoma.  
Lease Name Project Well No. 2  
Location E/2 of Sec. 5 Twp. 13 Rge. (E) (W)29  
County Gove Total Depth 1700  
Abandoned Oil Well Gas Well Input Well SWD Well D & A  
Other well as hereafter indicated STRATOGRAHIC TEST  
Plugging Contractor Abercrombie Drilling, Incorporated,  
Address 801 Union Center, Wichita, Kansas. License No.   
Operation Completed: Hour 7:00 PM Day 22 Month 11 Year 1967

The above well was plugged as follows:

320'—7" OD Surface casing cement circulated with 100 Sx. (6 1/4" Hole).  
Dakota section from 1460' to 1000'.

Circulated hole with heavy mud. Pulled DP to 1485' and displaced 100 Sx. cement thru  
DP from 1485' to 765'. Pulled DP to 372' and displaced 20 Sx. cement thru DP from  
372' to 220'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]  
Well Plugging Supervisor

INVOICED

DATE 11-29-67  
INV. NO. 6795-W