

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 30313
Name: JHL Energy, Inc
Address 1: 1428 Leecrest
Address 2: _____
City: Wichita State: KS Zip: 67209 + 1132
Contact Person: Alan Vratil
Phone: (620) 886-2419
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
Ft. Scott Depth to Top: 5097 Bottom: 5103 T.D. 5182
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 15-033-20994-00-00
Spot Description: _____
NW NW NW Sec. 15 Twp. 32 S. R. 19 East West
330 Feet from North / South Line of Section
330 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Comanche
Lease Name: Harold Herd Well #: 2-15
Date Well Completed: 2/28/1999
The plugging proposal was approved on: 9/30/2010 (Date)
by: Ken Jehlik (KCC District Agent's Name)
Plugging Commenced: 9/29/2010
Plugging Completed: 10/04/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		conductor	20"	90'	0
		surface csg	8 5/8"	728'	0
		prod csg	4 1/2"	5306'	3300'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set 4 1/2" CIBP @ 4995' and dumped 2 sxs of Portland cement w/ dump bailor. Stretch and cut csg @ 3300' and laid down. Ran tbg to 1070'. Quality Cementing pumped 12 sxs of gel and 50 sxs cement. Laid down tbg to 750' and pumped 50 sxs. Laid down tbg to 60' and circ. cement to surface w/ 40 sxs. Used 60/40 4% gel cement. RDMO.

AR

Plugging Contractor License #: 5105 Name: Clarke Corporation
Address 1: 107 W. Fowler Address 2: _____
City: Medicine Lodge State: KS Zip: 67104 + _____
Phone: (620) 886-5665
Name of Party Responsible for Plugging Fees: JHL Energy Inc.
State of KS County, Comanche, ss.
Alan Vratil Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Signature]

RECEIVED

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

OCT 08 2010

KCC WICHITA