

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 4058  
Name: American Warrior Inc.  
Address 1: P.O. Box 399  
Address 2: \_\_\_\_\_  
City: Garden City State: Ks. Zip: 67846 + \_\_\_\_\_  
Contact Person: Jody Smith  
Phone: (620) 275-2963  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Lansing Depth to Top: 2989' Bottom: 3232' T.D. 3400'  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 051-22726 00 00  
Spot Description: \_\_\_\_\_  
C SE SE SE Sec. 23 Twp. 11 S. R. 16  East  West  
330 Feet from  North /  South Line of Section  
330 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Ellis  
Lease Name: Bowby Well #: 1-23  
Date Well Completed: 9/1/82  
The plugging proposal was approved on: 3/22/11 (Date)  
by: Rich Williams (KCC District Agent's Name)  
Plugging Commenced: 4/29/11  
Plugging Completed: 4/29/11

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<u>Lansing/KC</u>	<u>oil</u>	<u>Surface</u>	<u>85/8</u>	<u>200'</u>	<u>0</u>
		<u>Production</u>	<u>41/2</u>	<u>NA</u>	<u>0</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf 1500', 940' and 475', 2spf. Ran tbg to 2957'. Swift hooked up to tbg, Pumped 100sx 60/40pos 4% gel w/ 200# hulls. Pulled tbg to 1525', Swift hooked up to tbg and pumped 180sx 60/40 pos, 4% gel. Cement circulated to surface. Pulled tbg. Swift hooked up to casing and topped off casing. Swift hooked up to 85/8 Pumped 20sx 60/40 pos 4% gel and shut in. Swift hooked up to 41/2, Pressured to 400# and shut in.

Plugging Contractor License #: 32382 Name: Swift Services Inc.  
Address 1: P.O. Box 466 Address 2: \_\_\_\_\_  
City: Ness City State: Ks Zip: 67560 + 0466  
Phone: (785) 798-2300

Name of Party Responsible for Plugging Fees: American Warrior Inc.  
State of Kansas County, Finney, ss.  
Jody Smith  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: 

RECEIVED

MAY 03 2011