

Notice: Fill out COMPLETELY  
and return to Conservation Division at  
the address below within  
60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 4058  
Name: American Warrior Inc.  
Address 1: P.O. Box 399  
Address 2: \_\_\_\_\_  
City: Garden City State: KS Zip: 67846 + \_\_\_\_\_  
Contact Person: Kevin Wiles  
Phone: (620) 275-2963  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
\_\_\_\_\_ Depth to Top: 4466 Bottom: 4468 T.D. 5452  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - 025-21412 00 00  
Spot Description: \_\_\_\_\_  
C SE SE NE Sec. 35 Twp. 32 S. R. 23  East  West  
2419 Feet from  North /  South Line of Section  
219 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Clark  
Lease Name: Bouziden Well #: 1-35  
Date Well Completed: 8/23/2007  
The plugging proposal was approved on: 4/11/2011 (Date)  
by: Steve Pfeifer (KCC District Agent's Name)  
Plugging Commenced: 4/20/2011  
Plugging Completed: 4/22/2011

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Conductor	13 3/8	333	None
		Surface	8 5/8	714	None
		Production	5 1/2	5110	2000

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set BP at 4400', spot 2sx cement with dump bailer on bridge plug, lay down casing, run tubing, 1st 1030', pump 15sx gel, 50sx 60/40 poz 4% gel, 2nd 730', 50sx cement, 3rd 300', 40sx cement, 4th 60' 20sx cement, circulate to surface

RECEIVED

MAY 03 2011

KCC WICHITA

Plugging Contractor License #: 5105 Name: Clarke Corporation  
Address 1: P.O. Box 187 Address 2: 107 W. Fowler  
City: Medicine Lodge State: KS Zip: 67104 + \_\_\_\_\_  
Phone: (620) 886-5665  
Name of Party Responsible for Plugging Fees: American Warrior  
State of Kansas County, Barber, ss.  
Mark Morgenstern  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark Morgenstern