

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 30705
Name: Younger Energy Company
Address 1: 453 S. Webb Road, Suite 100
Address 2: _____
City: Wichita State: KS Zip: 67207 + 1310
Contact Person: Diane Rebstock
Phone: (316) 681-2542
Type of Well: (Check one) Oil Well Gas Well ~~CO₂ Well~~ Cathodic
 Water Supply Well Other: LH SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No C-10 If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 083-10160-00-01
Spot Description: _____

SW NW Sec. 33 Twp. 23 S. R. 23 East West
1986 Feet from North / South Line of Section
613 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Hodgeman
Lease Name: Woods Well #: 2-3 OWWO
Date Well Completed: 8/6/2010
The plugging proposal was approved on: 8/6/2010 (Date)
by: Mike Myers (KCC District Agent's Name)
Plugging Commenced: 8/6/2010
Plugging Completed: 8/6/2010

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
RECEIVED OCT 05 2010 KCC WICHITA		Surface	8-5/8"	515'	none
		Production	5-1/2"	4801'	original drill 3121.29'
			5-1/2"	3121'	OWWO pulled 747'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ran a tapered tap and slip collar to join old 5-1/2" csg left in well @ 3121' with 5-1/2' csg ran during OWWO operation. While washing down the older portion of 5-1/2" csg @ 3390', encountered either parted csg or got out of the old pipe so abandoned effort to complete OWWO operation and plugged well. Shot off 5-1/2" production casing at 747'. Plugged with total of 140 sxs 60/40 pozmix, 4% gel. Pumped 25 sxs @ 3100', disp w/35 bbls. Pumped 100 sxs @ 700', disp w/5 bbls. Topped off w/15 sxs.

Plugging Contractor License #: 6426 Name: Express Well Service & Supply, Inc.
Address 1: P.O. Box 19 Address 2: _____
City: Victoria State: KS Zip: 67671 + 0019
Phone: (785) 735-9405
Name of Party Responsible for Plugging Fees: Younger Energy Company, 453 S. Webb Rd., Suite 100, Wichita, KS 67207
State of Kansas County, Sedgwick, ss.
Diane Rebstock Employee of Operator or Operator on above-described well.
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Diane Rebstock

