

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 4058
Name: American Warrior INC
Address 1: P.O.Box 399
Address 2: _____
City: Garden City State: KS Zip: 67846 + _____
Contact Person: Kevin Wiles SR
Phone: (620) 275-2963
Type of Well: (Check one) ☐ Oil Well ☐ Gas Well ☐ OG ☐ D&A ☐ Cathodic
☐ Water Supply Well ☐ Other: _____ ☒ SWD Permit #: D-28,554
☐ ENHR Permit #: _____ ☐ Gas Storage Permit #: _____
Is ACO-1 filed? ☒ Yes ☐ No If not, is well log attached? ☐ Yes ☒ No
Producing Formation(s): List All (if needed attach another sheet)
Chase Depth to Top: 2368 Bottom: 2458 T.D. 2570
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 007-22,411-0002
Spot Description: SW--11-32s-15w
SE - NE - SW - Sec. 11 Twp. 32 S. R. 15 ☐ East ☒ West
1,490 Feet from ☐ North / ☒ South Line of Section
2,790 Feet from ☒ East / ☐ West Line of Section
Footages Calculated from Nearest Outside Section Corner:
☐ NE ☐ NW ☐ SE ☒ SW
County: Barber
Lease Name: Alexander Well #: N-1
Date Well Completed: 7-25-01
The plugging proposal was approved on: 10-8-10 (Date)
by: Steve Durant (KCC District Agent's Name)
Plugging Commenced: 10-11-10
Plugging Completed: 10-11-10

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	240	None
		Production	4-1/2"	2598	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIPB @ 2300', Dump 2 sks cement on plug, perf 4- holes @ 630', hook-up to csg. break cir.
pump 250 sks 60/40 poz, 4% gel cement, circulated 20 sks cement to pit, SI. w/ 150#s, Job Complete.

RECEIVED

OCT 19 2010

KCC WICHITA

Plugging Contractor License #: 99996 Name: Allied Cementing Co.
Address 1: P.O.Box 31, Address 2: _____
City: Russell State: KS Zip: 67665 + _____
Phone: (785) 483-2627
Name of Party Responsible for Plugging Fees: American Warrior INC
State of Kansas County, Barber ss. _____
Kevin Wiles SR ☒ Employee of Operator or ☐ Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____