

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-195-21,703-00-00 (of this well) 6/86
(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Held By Production, Inc./SETCO (joint) OPERATORS LICENSE NO. 8362(HBP)
4000(SETCO)

ADDRESS 1625 Bbroadway, Suite 410, Denver, CO 80202 PHONE # (303) 534-4445

LEASE (FARM) Kroeger WELL NO. 23-9"D" WELL LOCATION SE NE SE COUNTY Trego

SEC. 23 TWP. 13S RGE. 21W (S) or (W) TOTAL DEPTH 4050' PLUG BACK TO 3982'

Check One: *4½" csg set on 10/4/85. Marmaton completion unsuccessful.

OIL WELL GAS WELL D & A X* SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8-5/8" SET AT 257' CEMENTED WITH 165 SACKS 60/40 pozz.

CASING SIZE 4½" SET AT 4049' CEMENTED WITH 375 sx Econolite SACKS + 125
sx 60/40 Pozz.

PERFORATED AT 3863'-3900' w/ 2 ispf

CONDITION OF WELL: GOOD X (new) POOR CASING LEAK JUNK IN HOLE

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL 4½ csg was cemented back to surface w/ good
returns. Suggest 50 sx 50/50 pozz w/ 3 sx hulls, 6% gel & 3% CaCl₂ + 37 bbl gel mud + 50 sx
50/50 pozz w/ 6% gel & 3% CaCl₂. Run wiper plug between gel & top cement.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? YES
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN arrange w/ local office after 12/1/85

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND
REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Marc T. Eckels PHONE # (303) 534-4445

ADDRESS same as above

PLUGGING CONTRACTOR Halliburton LICENSE NO. 5287

ADDRESS 1100 East 8th, Hays KS 67601 PHONE # (913) 625-3431

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: [Signature]
STATE CORPORATION COMMISSION (Operator or Agent)

(6) DEC 9 1985 DATE: 11/26/85



JOHN CARLIN
MICHAEL LENNEN
MARGALEE WRIGHT
KEITH R. HEALEY
JUDITH A. McCONNELL
BRIAN J. MOLINE

Governor
Chairman
Commissioner
Executive Secretary
General Counsel

State Corporation Commission
CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

KAR 9 1986

December 9, 1985

EXPIRES

WELL PLUGGING NOTICE

Kroeger 23-9 "D"
SE NE SE
Sec. 23-13S-21W
Trego County

Held By Production, Inc./SETCO
1625 Broadway, Ste. 410
Denver, CO 80202

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This notice is void after ninety (90) days from the above date.

Sincerely,

William R. Bryson

William R. Bryson, Director

Please submit your proposal for plugging the above captioned well to
DIST. #6 1014 Cody Hays, KS 67601 913-628-1200

five days prior to plugging the well (KAR-82-3-113).