

15-195-20100-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 28 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Tilco, Et al.,

Complete Address: 815 Wichita Plaza Building, Wichita, Kansas.

Lease Name Egger Well No. 3

Location NE-NW-NE Sec. 20 Twp. 13 Rge. (E) (W) 21

County Trego Total Depth 4025'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Leben Drilling, Incorporated,

Address: Box #486, Great Bend, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 3:30 AM Day 25 Month 1 Year 1969

The Above well was plugged as follows:

237'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 700'.

Circulated hole with heavy mud. Pulled DP to 950' and displaced 100 Sx. cement thru  
DP from 950' to 625'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from  
240' to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols  
Well Plugging Supervisor

DATE 1/28/69  
INV. NO. 9245-W