



KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 19 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Tilco, Et al.

Complete Address: 815 Wichita Plaza Building, Wichita, Kansas.

Lease Name Eggar Well No. 4

Location SW-NE-NE Sec. 20 Twp. 13 Rge. (E) (W) 21

County Trego Total Depth 4022'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Leben Drilling, Incorporated.

Address: Box #486, Great Bend, Kansas. License No. _____

Operation Completed: Hour 6:30 AM Day 11 Month 3 Year 1969

The Above well was plugged as follows:

218'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 525'.

Circulated hole with heavy mud. Pulled DP to 750' and displaced 100 Sx. cement thru
DP. Pulled DP to 245' and displaced 20 Sx. cement thru DP from 245' to 185'. Pulled
DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 3/19/69
INV. NO. 9480-W