

15-195-20157-00-00

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
SEP 4 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Leo J. Dreiling Oil Company,

Complete Address R. R. #2, Victoria, Kansas.

Lease Name Glass Well No. 2

Location SW-NE-NE Sec. 7 Twp. 13 Rge. (E) (W) 21

County Trego Total Depth 4000'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Russ Casing Pulling, Incorporated,

Address Box #1082, Great Bend, Kansas. License No. 623

Operation Completed: Hour 11:00 AM Day 1 Month 9 Year 1970

The above well was plugged as follows:

187'--8 5/8" Surface casing, cement circulated with 150 Sx.
3932'--4 1/2" Production casing cemented on bottom with 150 Sx. Top perforations C
3755'.

Sanded well back to 3725' and set 4 Sx. cement with dump bailer. Pulled 4 1/2" casing
and squeezed well initially with 5 sacks hulls and 10 sacks gel and followed with 100
Sx. cement from 825' to 500' then 7 sacks gel from 500' to 200' and followed with 25
Sx. cement from 200' to 125' then 3 sacks gel from 125' to 30' and finally 10 Sx.
cement from 30' to bottom of cellar. Maximum pump-in pressure-400#, FSI-100#.
Recovered 3190' 4 1/2" casing. (Ludding and cementing operations by Sun Cementing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. L. Nichols
Well Plugging Supervisor

DATE 9-4-70
INV. NO. 2478-W