

15-195-00276-00-00

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. _____

LOCATION SE SE SW

SEC. 7 TWP. 13 RGE. 21

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease _____ Beach _____

Operator Continental Oil Co Address Box 98 Plainville, Kans

Field _____ County Trego

Total Depth 4150 Feet.

Plugging Contractor Garvey Drg Co & Globe Cementing Co

Plugging Contractor's License No. _____

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 250', circulated with cement.

Gunned pits, circulated hole with heavy mud, set cementing plug at
700', displaced 25 sax cement through drill pipe, heavy mud to 240',
set cementing plug and displaced 25 sax cement through drill pipe,
heavy mud to 40', set cementing plug, 1/2 sack hulls and 10 sax cement
to bottom cellar.

Cementing by Globe Cementing Co.

Edward Petty
District Conservation Agent

Date 8-16-57

RECORDED
STATE CORPORATION COMMISSION

PLUGGING
FILE SEC. 7 T. 13 R. 21W
BOOK PAGE 38 LINE 45

AUG 20 1957

CONSERVATION DIVISION
Wichita, Kansas