

15-195-20302-00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
OCT 9 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Donald C. Slawson,
Complete Address 408 One-Twenty Building, Wichita, Kansas.
Lease Name Morton Well No. A-1
Location NW-NE-SE Sec. 7 Twp. 13 Rge. (E) (W)21
County Trego Total Depth 4032'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Slawson Drilling Company, Incorporated,
Address Above License No.
Operation Completed: Hour 6:15 PM Day 5 Month 10 Year 1974

The above well was plugged as follows:

246'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 550'.
Circulated hole with heavy mud. Pulled DP to 775' and displaced 110 Cu. Ft. cement
thru DP from 775' to 450'. Pulled DP to 250' and displaced 30 Cu. Ft. cement thru
DP from 250' to 175'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement from 40' to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. S. Nichols
Well Plugging Supervisor

INVOICED

DATE 10/9/74
INV. NO. 74-W