

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

NOV 17 1977

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

CONSERVATION DIVISION
Wichita, Kansas

API Number 15 - 195 - 00920 - 00 - 0 of this well)

Operator's Full Name Phillips Petroleum Co.

Complete Address 7th Floor Phillips Bldg. Bartlesville Okla.

Lease Name Arnold "A" Well No. 1

Location NE-NW-NW Sec. 23 Twp. 13 Rge. 21 (E) (W) X

County Trego Total Depth 3942

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase Ks. License No. 683

Operation Completed: Hour 2:30 PM Day 15 Month Nov Year 1977

The above well was plugged as follows:

TD. 3942. Plug. Back 3795. KB. 2278. Dak. Top. 1750
Perf 3588' to 3764. 5 1/2" casing. Set @ 3940' 8 5/8" S.P.
230' cwc. Bottom Plug. w/ 60 sa. cem 3795 to 3488'
Gel. 25. sa. 3488' to 2300' Recovered 376' of 5 1/2" casing.
2, Stage 5 1/2" casing @ 1645' w/ 475. sa. cem. Pumped down
8 5/8" S.P. 100 sa. cem. 50/50 Formix 6? Gel. No Pressure. By Sun.
Settle to 327' Filled To Surface. w/ 4 yd. of Red. Mix

I hereby certify that the above well was plugged as herein stated.

Signed: Jillup Balthazar
Well Plugging Supervisor

INVOICED

DATE 11-17-77

INV. NO. 6222 W