

15-195-00921-00-00

Form CP-3
Rev. 6-26-62

10
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 16 1965
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Birmingham and Bartlett Drilling Company,

Complete Address: 300 Kaufman Building, Wichita, Kansas.

Lease Name Arnold Well No. A-2

Location NW-NW-NW Sec. 23 Twp. 13 Rge. (E) (W) 21

County Trego Total Depth 3973'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Santa Fe Pipe and Supply, Incorporated,

Address: Box #562, Great Bend, Kansas. License No. 574

Operation Completed: Hour 5:00PM Day 10 Month 11 Year 1965

The Above well was plugged as follows:

237'--8 5/8" Surface pipe, cement circulated.

3972'--5 1/2" Production casing cemented with 150 Sx. Top perforations from 3602 to 3608'.

Sanded well back to 3590' and set 4 Sx. cement with dump bailer. Pulled

5 1/2" casing to 600' and circulated heavy gel mud. (Used 16 Sx. gel) Dis-

placed 20 Sx. cement thru 5 1/2" @ 600'. Pulled 5 1/2" to 240' and displaced 20

Sx. cement thru 5 1/2". Pulled 5 1/2", set bridge C 35' and 10 Sx. cement to

bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: W. L. Nichols
Well Plugging Supervisor

DATE 11/16/65

INV. NO. 2188-W