

15-~~0~~<sup>195</sup>-20101-00-00

Form CP-3  
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 26 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
02-26-1969

Operator's Full Name Tilco, Et, al,  
Complete Address: 815 Wichita Plaza Building, Wichita, Kansas,  
Lease Name Keller Well No. 1  
Location SW-SW-SW Sec. 16 Twp. 13 Rge. (E) (W) 21  
County Trego Total Depth 3972'  
Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X  
Other well as hereafter indicated:       
Plugging Contractor: Leben Drilling, Incorporated,  
Address: Box #186, Great Bend, Kansas, License No.       
Operation Completed: Hour 4:00PM Day 21 Month 2 Year 69

The Above well was plugged as follows:

226'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 725'.  
Circulated hole with heavy mud. Pulled DP to 950' and displaced 100 Sx. cement thru  
DP from 950' to 625'. Pulled DP to 240' and displaced 20 Sx. cement thru DP from 240'  
to 180'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Dichek  
Well Plugging Supervisor

DATE 2/26/69  
INV. NO. 9383-W