

15-~~195~~¹⁹⁵ - 20209-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

04-03-1972
RECEIVED
STATE CORPORATION COMMISSION
APR 3 - 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Tenneco Oil Company,
Complete Address 2000 Classen Center-East Building, Oklahoma City, Okla.
Lease Name V. M. Nelson Well No. 1-16
Location NE-NE-SE Sec. 16 Twp. 13 Rge. (E) (W) 21
County Trego Total Depth 4005'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Garvey Drilling Company,
Address Box #1164, Great Bend, Kansas. License No.
Operation Completed: Hour 4:30 PM Day 31 Month 3 Year 1972

The above well was plugged as follows:

208'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 675'.
Circulated hole with heavy mud. Pulled DP to 900' and displaced 110 Cu. Ft. cement
thru DP from 900' to 575'. Pulled DP to 200' and displaced 30 Cu. Ft. cement thru
DP from 200' to 125'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Dickels
Well Plugging Supervisor

INVOICED

DATE 4-3-72
INV. NO. 5480-W