

15-195-20248-00-00

P

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 1973
CONSERVATION DIVISION
10-05-1973

Operator's Full Name Pickrell Drilling Company,

Complete Address 705 Fourth National Bank Building, Wichita, Kansas.

Lease Name Petty Well No. C-2

Location NW-SE-SW Sec. 19 Twp. 13 Rge. (E) (W) 21

County Trego Total Depth 4140'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 11:30 AM Day 2 Month 10 Year 1973

The above well was plugged as follows:

263'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 625'.

Circulated hole with heavy mud. Pulled DP to 850' and displaced 110 Cu. Ft. cement
thru DP from 850' to 525'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

INVOICED

I hereby certify that the above well was plugged as herein stated.

DATE 10/5/73

INV. NO. 7979-10

Signed: H. L. Pickrell
Well Plugging Supervisor