

15-~~001~~¹⁹⁵-20278-00-00



Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1974
05-13-1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Pickrell Drilling Company,

Complete Address 705 Fourth National Bank Building, Wichita, Kansas.

Lease Name Herbert Well No. A-1

Location S/2-SW-NW Sec. 19 Twp. 13 Rge. (E) (W) 21

County Trego Total Depth 4070'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Strata Drilling, Incorporated,

Address Box #355, Great Bend, Kansas. License No.

Operation Completed: Hour 10:30 PM Day 10 Month 5 Year 1974

The above well was plugged as follows:

209'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 575'.

Circulated hole with heavy mud. Pulled DP to 800' and displaced 110 Cu. Ft. cement
thru DP from 800' to 475'. Pulled DP to 215' and displaced 30 Cu. Ft. cement thru
DP from 215' to 140'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED
DATE 5/15/74
INV. NO. 9119-W