

15-195-20865-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Trego SEC. 2 TWP. 13S RGE. 22W E/W  
Location as in quarters or footage from lines:  
NW/4 SE/4 SE/4


Lease Owner Hummon Corporation  
Lease Name King Well No. 1  
Office Address 400 One Main Place, Wichita, Kansas 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): D & A  
Date Well Completed August 21, 1981  
Application for plugging filed August 21, 1981  
Plugging commenced August 21, 1981  
Plugging completed August 21, 1981  
Reason for abandonment of well or producing formation D & A

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gil Balthazor

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 4,090'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	257.94'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Plugged hole  
1st plug @ 800' w/60 sx cement  
2nd plug @ 260' w/40 sx cement  
Bridge plug @ 40' w/10 sx cement  
5 sx cement in rathole  
50/50 Pozmix, 6% Gel

RECEIVED  
STATE CORPORATION COMMISSION  
08-28-1981  
AUG 28 1981

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Red Tiger Drilling Company  
1720 KSB Building, Wichita, Kansas 67202 Wichita, Kansas

STATE OF Kansas COUNTY OF Sedgwick, ss. \_\_\_\_\_ contractor  
Gloria Fawcett (employee of ~~owner~~) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) Gloria Fawcett  
1720 KSB Building, Wichita, Ks. 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of August, 19 81.

Joyce A. Baer  
Notary Public.

My Commission expires: \_\_\_\_\_



KANSAS

WELL COMPLETION REPORT AND DRILLER'S LOG


API No. 15 — 195 County — 20,865 Number 00-00

S. 2 T. 13S R. 22W E W

Loc. NW/4 SE/4 SE/4

County Trego

640 Acres N



Locate well correctly

Elev.: Gr. 2274

DF 2276 KB 2279

Operator  
Hummon Corporation

Address  
400 One Main Place, Wichita, KS 67202

Well No. 1 Lease Name King

Footage Location  
990 feet from (N) (S) line 990 feet from (E) (W) line

Principal Contractor Red Tiger Drilling Company Geologist John Carnes

Spud Date 8/10/81 Date Completed 8/21/81 Total Depth 4,090' P.B.T.D.

Directional Deviation Oil and/or Gas Purchaser

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	266.94'	Common	165 sx	2% Gel, 3% CC

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

RECEIVED  
AUG 28 1981  
08-28-1981  
CONSERVATION DIVISION  
Wichita, Kansas

INITIAL PRODUCTION

Date of first production Producing method (flowing, pumping, gas lift, etc.)

RATE OF PRODUCTION PER 24 HOURS  
Oil Gas Water Gas-oil ratio  
bbls. MCF bbls. CFPB

Disposition of gas (vented, used on lease or sold) Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator  
Hummon Corporation

DESIGNATE TYPE OF COMP.: OIL, GAS,  
DRY HOLE, SWDW, ETC.:  
Dry Hole

Well No. 1 Lease Name King

S 2 T13S R 22W E W

**WELL LOG**

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
			LOG	TOPS
DST #1: 3706-3752' OP 30/45/30/45 Strong blow thruout Rec. 590' Muddy salt water		FP 100-192, 247-329 SIP 577-577	Top Anhyd. Base Anhyd. Heebner	1705 + 574 1755 + 524 3593 -1314
DST #2: 3960-3990' OP 30/30/30/30 Rec. 15' SOCM		FP 64-64, 73-73 SIP 1045-1045	Toronto Lansing B/KC	3614 -1335 3628 -1349 3866 -1587
DST #3: 4003-4042' OP 30/45/30/60 Rec. 20' OSM		All flow pressures 73 SIP 788-744	T. Marmaton Cher Sd 2nd Cong Sd LTD	3954 -1675 4039 -1760 4054 -1755 4089
DST #4: 4040-4061' OP 30/45/30/60 Rec. 20' mud Weak blow, died in 19"		FP 54-54, 73-73 SIP 1174-1119		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

*Wilber O Berg*  
Signature

Title

Date