


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Trego County. Sec. 36 Twp. 13 Rge. 21 (E) X (W)  
Location as "NE/CNW/SW" or footage from lines NW NW SE  
Lease Owner Leo J. Dreiling Oil Company  
Lease Name Kroeger Well No. 1  
Office Address Victoria, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) D. A.  
Date well completed 6/2/64 19\_\_  
Application for plugging filed 6/2/64 19\_\_  
Application for plugging approved 6/2/64 19\_\_  
Plugging commenced 6/2/64 19\_\_  
Plugging completed 6/2/64 19\_\_  
Reason for abandonment of well or producing formation -0-

If a producing well is abandoned, date of last production -0- 19\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty  
Producing formation -0- Depth to top -0- Bottom -0- Total Depth of Well 4000' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe				8 5/8"	225'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Rotary mud was used to fill hole to a depth of 550' were 1st plug was set using 20 sacks cement, filled hole with rotary mud to a depth of 210' were 2nd plug was set using 20 sacks cement, filled hole to a depth of 40' were 3rd plug was set using 10 sacks cement and filled hole to surface.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 16 1964  
06-16-1964  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. J. Dreiling & Sons, Inc.  
Address Victoria, Kansas

STATE OF Kansas COUNTY OF Ellis, ss.  
I, Leo F. Dreiling a partner of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo F. Dreiling  
Leo F. Dreiling

(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of June, 19 64

My commission expires August 14, 1965

Ronald Zimmerman  
Notary Public.

L. J. DREILING and SONS, Inc.  
VICTORIA, KANSAS

WELL LOG

Company Leo J. Dreiling Oil Company  
Victoria, Kansas

Sec. 36 Twp. 13 Rng. 21

Farm Kroeger No1

Location NW NE SE

Total Depth 4000'

County Trego County, Kansas

Comm. 5/25/64 Comp. 6/2/64

Elevation: D. F.

Contractor L. J. DREILING & SONS, INC.  
VICTORIA, KANSAS

G. R.

Casing Record

Cement Record

Production:

225' - - - - 8 5/8"

150 sacks cement

D. & A.

Figures Indicate Bottom of Formations

0 - 50	Surface Clay
50 - 225	Clay & Shale
225 - 1110	Shale & Shells
1110 - 1340	Sand
1340 - 1516	Shale
1516 - 1635	Shale
1635 - 1682	Anhydrite
1682 - 2187	Shale
2187 - 2360	Shale & Lime
2360 - 2630	Shale & Shells
2630 - 2770	Lime & Shale
2770 - 3105	Lime & Shale
3105 - 3465	Lime
3465 - 3522	Lime
3522 - 3629	Lime
3629 - 3665	Lime
3665 - 3715	Lime
3715 - 3835	Lime
3835 - 3927	Lime
3927 - 3958	Lime
3958 - 3990	Lime
3990 - 4000	Lime
4000	TD

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 16 1964  
06-16-1964  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) ss.  
COUNTY OF ELLIS )

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Kroeger #1.

*Leo F. Dreiling*  
LEO F. DREILING

Subscribed and sworn to before me this 13th day of June, 1964.

*James Zimmerman*  
NOTARY PUBLIC

My Commission Expires: August 14, 1965