

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21,573-00-0

LEASE NAME Schmeidler

WELL NUMBER 1

SPOT LOCATION NE NE NW

SEC. 36 TWP. 13S RGE. 21 (XXX)(W)

COUNTY Trego

Date Well Completed 8/25/84

Plugging Commenced 8/25/84

Plugging Completed 8/25/85

*Rec'd
09-05-1984*

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Mid-America Minerals

ADDRESS P. O. Box 518, Hays, KS 67601

PHONE # (913) 628-1115 OPERATORS LICENSE NO. 7601

Character of Well D & A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District #6 Dave Wann

Is ACO-1 filed? no If not, is well log attached? yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 4,015'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	226'	--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Mud to 4,005', 20 sx cement, mud to 1,640', 20 sx cement,
mud to 910', 100 sx cement, 1 sx flow seal, mud to 260'
40 sx cement, mud to 40', solid bridge, 10 sx cement, 10 sx
cement in rathole, 50/50 posmix, 6% gel, 3% cc

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sun Oil Well Cementing License No. _____
Address Box 169, Great Bend, KS 67530


STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Donald E. Hunt (employee of operator) ~~is~~
~~copy of~~ of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) Donald E. Hunt

(Address) Suite 250, 200 W. Douglas
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 4th day of September, 19 84



Kathleen L. Greger
Notary Public

My Commission expires: January 20, 1985

Kathleen L. Greger

15-195-21573-00-00

DRILLERS LOG

#1 Schmeidler
NE NE NW Section 36-13S-21W
Trego County, Kansas

OPERATOR: MID-AMERICA MINERALS
P. O. Box 518
Hays, KS 67601

CONTRACTOR: WILDCAT DRILLING COMPANY
Suite 250, 200 W. Douglas
Wichita, KS 67202

COMMENCED: August 18, 1984.

COMPLETED: August 25, 1984

CASING RECORD: 8-5/8" @ 226' w/150 sx 60/40 posmix


<u>FROM</u>	<u>TO</u>	<u>DESCRIPTION</u>
0	2110	Sand and shale
2110	2730	Shale
2730	4015	Lime and shale
4015		Rotary total depth

STATE OF KANSAS)
) ss
COUNTY OF SEDGWICK)

I hereby certify that the above is a true and correct log to the best of my knowledge and belief.

Donald E. Hunt
Donald E. Hunt

Subscribed and sworn to before me this 4th day of September, 1984.



My appointment expires:
January 20, 1985

Kathleen L. Greger
Kathleen L. Greger, Notary Public

RECEIVED
STATE CORPORATION COMMISSION

SEP 05 1984

CONSERVATION DIVISION
Wichita, Kansas

09-05-1984