

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-21,505-00-00

LEASE NAME Bongartz #1

WELL NUMBER _____

SPOT LOCATION 150' SE C of SW NE

SEC. 30 TWP. 13 RGE. 2 W (E) or (W)

COUNTY Trego

Date Well Completed _____

Plugging Commenced 10/29/84

Plugging Completed 11/2/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR W.L. Kirkman, Inc.

ADDRESS 453 S. Webb Rd. Suite 100, Wichita, Ks. 67218

PHONE # (316) 685-5372 OPERATORS LICENSE NO. 5673

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4185'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	294'	none
				5 1/2"	4155'	3434'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Plugged bottom with 5 sacks cement, sand to 4175' & 5 sacks cement. Shot pipe at 3434'
Pulled 86 joints of pipe. Plugged well with 5 gel with 1 hull, 40 cement with 1 hull,
10 gel with 1 hull, 100 cement with 2 hulls, 10 gel with 1 hull, ~~relined~~ Plug, & 50 cement.
Plugging complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050
Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

RECEIVED
STATE CORPORATION COMMISSION


NOV 07 1984
CONSERVATION DIVISION
Wichita, Kansas

R. Darrell Kelso (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 5th day of November, 1984



Irene Hoover
Notary Public

My Commission expires: _____

ALDEBARAN

453 SOUTH WEBB ROAD
P.O. BOX 18611
WICHITA, KANSAS 67207
(316) 685-5372

15-195-21505-00-00

WELL LOG



WELL NAME: Bongartz #1

WELL LOCATION: 150' SE of CSW,
NE, Sec. 30-13S-21W, Trego, Co.

OPERATOR: W.L. Kirkman, Inc.

COMMENCED: May 23, 1984

CONTRACTOR: Aldebaran Drilling Co., Inc.

COMPLETED: June 2, 1984

175 Sacks class A,
CASING RECORD: 3% CC. 8 5/8" casing
set at 294'.
5 1/2" casing set at 4155'.
60.40 Poz, Salt 2%, .75% CFR 2

FORMATION:

	FROM:	TO:
Clays - Sand	0	711'
Shales	711'	2174'
Lime - Shales	2174'	4065'
Shales	4065'	4068'
Shales -Cherokee Sands	4068'	4095'
Cherokee Sands	4095'	4125'
Arbuckle	4125'	4135'
Shale & Lime	4135'	4185'

STATE OF KANSAS)
COUNTY OF SEDGWICK) SS:

I CERTIFY THAT THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG ON THE WELL DRILLED
150' SE of CSW, NE, Sec. 30-13S-21W, Trego, County, Kansas TO THE BEST OF MY
KNOWLEDGE AND BELIEF.

OCT 16 1984

ALDEBARAN DRILLING CO., INC.

Wayne L. Kirkman
Wayne L. Kirkman - President

SUBSCRIBED AND SWORN TO BEFORE ME THIS 5th DAY OF June, 1984

MY APPOINTMENT EXPIRES: March 20, 1987

KATHLEEN G. QUINN
STATE NOTARY PUBLIC
Sedgwick County, Kansas
My Appt. Exp 3-20-87

Kathleen G. Quinn
Kathleen G. Quinn NOTARY PUBLIC