

WELL PLUGGING RECORD

15-195-21111-00-00

Give All Information Completely
 Make Required Affidavit

COUNTY Trego SEC. 30 TWP. 13S RGE. 21W E/W
 Location as in quarters or footage from lines:
NESESE 990' FSL, 330' FEL

			XX

Locate Well
 correctly on above
 Section Platt.

Lease Owner SWENCO-Western, Inc.
 Lease Name F. Bongartz Well No. 1-30
 Office Address 1337 Delaware St. Ste. 200 Denver, CO 80204
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed 11/23/82
 Application for plugging filed 1/2/87
 Plugging commenced 1/5/87
 Plugging completed 1/5/87
 Reason for abandonment of well or producing formation Resources depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dale Balthazor
 Producing formation Cherokee Depth to top 4092 bottom 4114 T.D. 4238

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Cherokee	oil	4094-	4157	8 5/8 4 1/2	253'-4238' to 4196'	

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from feet
 to feet for each plug set. Pumped in 10 sx of cement, pressure to 400 Psi.
Annulus held o.k. RI on 1 1/2" csg, pump in rate 2000 Psi @ 2 bbls/min. Pumped in a total
of 180 sx 60/40 poz w/ 2% Econolite & 10% gel. Final pressure 1200 Psi @ 1 bbl/min. SD
Well bled to 0 Psi. WOC 1 hr. Tagged cement w/ fishing line @ 300' in 4 1/2" csg.
Pumped in 5 sx of cement @ top (gravity feet). Cement stayed @ surf. Cemented
wellhead 5' below G.L., cleaned location.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

STATE OF Colorado COUNTY OF Denver, ss.
SWENCO-Western, Inc. (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) Thomas W. Talbert
 Thomas W. Talbert, President
 (Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of March, 1987
 1337 Delaware St. Ste. 200

My Commission expires: March 3, 1990

Lori K. Crosby
 1337 Delaware St. Ste. 200R
 Denver, CO 80204

RECEIVED
 STATE CORPORATION COMMISSION
 NOTARY PUBLIC
 03-03-87
 CONSERVATION DIVISION
 WICHITA, KANSAS