

WELL PLUGGING RECORD

15-195-21089-00-00

Give All Information Completely  
 Make Required Affidavit

COUNTY Trego SEC. 31 TWP. 13S RGE. 21W E/W  
 Location as in quarters or footage from lines:  
NENENE

			XX

Lease Owner SWENCO-Western, Inc.  
 Lease Name G. Bongartz Well No. 1  
 Office Address 1337 Delaware St. Ste. 200 Denver, CO 80204  
 Character of Well (Completed as Oil, Gas or Dry Hole): oil  
 Date Well Completed 1/19/83  
 Application for plugging filed 1/2/87  
 Plugging commenced 1/5/87  
 Plugging completed 1/5/87  
 Reason for abandonment of well or producing formation Resources depleted

Locate Well  
 correctly on above  
 Section Platt.

Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Dale Balthazor  
 Producing formation Cherokee Depth to top 4110 bottom 4130 T.D. 4196  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Cherokee	oil	4110	4130	8 5/8 4 1/2"	249-4196' to 4157'	

Describe in detail the manner in which the well was plugged, indicating where the mud  
 fluid was placed and the method or methods used in introducing it into the hold. If cement  
 or other plugs were used, state the character of same and depth placed, from        feet  
 to        feet for each plug set. RU Halliburton, pumped in 5 sx cem. Held 400 Psi  
for 15 minutes. Annulus held o.k. RU on 4 1/2" csg w/ Halliburton. Pumped in rate @ 500  
Psi @ 2 bbls/min. Pumped in a total of 125 sx in casing of 60/40 poz. w/ 2% Econolite  
w/ 10% gel. Final pressure 2900 Psi, bled to 2800 Psi, SI for 1 hr. Top of cem  
5' below GL.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton

STATE OF Colorado COUNTY OF Denver, ss.  
SWENCO-Western, Inc. (employee of owner) or (owner or operator) of the  
 above-described well, being first duly sworn on oath, says: That I have knowledge of the  
 facts, statements, and matters herein contained and the log of the above-described well as  
 filed and that the same are true and correct. So help me God.

(Signature) Thomas W. Talbert  
Thomas W. Talbert, President  
1337 Delaware St. Ste. 200  
Denver, CO 80204

SUBSCRIBED AND SWORN TO before me this 2nd day of March, 19 87

Lori K Crosby  
 RECEIVED  
 STATE CORPORATION COMMISSION  
 Notary Public.  
 1337 Delaware St. Ste. 200  
 Denver, CO 80204  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 03-09-87

My Commission expires: March 3, 1990