


15-195-20247-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

ALL INFORMATION CONTAINED
HEREIN IS UNCLASSIFIED
DATE 08-01-2011 BY 60322
MAIL ROOM/STATE ARCHIVE
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217



Locate well correctly on above
Section Plat

Trego County, Sec. 30 Twp. 13, Rge. 21 (E) (W)
Location as "NE/4NW/4SE/4" or footage from lines NW SE NE
Lease Owner Rains & Williamson Oil Co.
Lease Name Flax #1 Well No.
Office Address Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 10
Application for plugging filed 10
Application for plugging approved 10
Plugging commenced 5/28/74 10
Plugging completed 5/31/74 10
Reason for abandonment of well or producing formation depleted.
If a producing well is abandoned, date of last production 10
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Nichols
Producing formation Depth to top Bottom Total Depth of Well 4150 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	246	none
				5 1/2"	4149'	3298'

'CASING RECORD

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 4120' and dumped 5 sacks cement.
Shot pipe at 3398', 3366', worked pipe loose and pulled 102 joints. Allied pumped 5 sacks hulls, 25 sacks gel and 150 sacks cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUN 7 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.
Address CHASE, KANSAS

STATE OF KANSAS (COUNTY) OF RICE
NOEL J. KNIGHT ss.

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS (Address)

Subscribed and sworn to before me this 5th day of June 10, 74

MARGARET MELCHER
NOTARY PUBLIC
Rice County, Kansas
My Commission Expires
Feb. 15, 1975

Margaret Melcher
Notary Public.

WELL LOG

15-195-20247-00-00

COMPANY Rains & Williamson Oil Co., Inc.

SEC. 30 T. 13S R. 21W

FARM Flax NO. 1

LOC. NW SE NE


RIG. NO. 4

COUNTY Trego KANSAS

TOTAL DEPTH 4150

COMM. 8-24-73

COMP. 9-2-73



CONTRACTOR Rains & Williamson Oil Co., Inc.

CASING

20 10
15 8 5/8" @ 246' w/ 160 sx. 2% gel, 3% cc.
12 6
13 5 1/2" @ 4149' w/ 125 sx. common, 18% salt,
3/4 of 1% CFR2

ELEVATION 2339 KB

PRODUCTION Oil

FIGURES INDICATE BOTTOM OF FORMATIONS

Clay, Sand and Shale	240
Shale	815
Shale, Sand and Shale	1639
Shale and Red Bed	1755
Anhydrite	1796
Shale	2010
Shale and Lime	2500
Lime and Shale	2860
Shale and Lime	3030
Lime and Shale	3540
Shale and Lime	3638
Lime	4110
Conglomerate	4150
<u>Rotary Total Depth</u>	<u>4150</u>

RECEIVED
STATE CORPORATION COMMISSION
OCT 3 1975
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS
County of SEDGWICK } ss:

I, Wilson Rains, President of the Rains & Williamson Oil Co., Inc. ~~Notary~~

upon oath state that the above and foregoing is a true and correct copy of the log of the Flax #1 well.

Wilson Rains
WILSON RAINS



Subscribed and sworn to before me this 6th day of September 19 73

My Commission Expires: October 4, 1975

Juanita M. Green
NOTARY PUBLIC
Juanita M. Green