

STATE CORPORATION COMMISSION  
202 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 195-22185-0000

CASE NAME Bongartz "A"

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

WELL NUMBER 1  
1980 Ft. from S Section Line  
1980 Ft. from E Section Line  
SEC. 30 TWP. 13S RGE. 21 ~~X0E1~~ or (W)  
COUNTY Trego

LEASE OPERATOR Castle Resources, Inc.  
ADDRESS 1200 East 27th # C Hays, Kansas 67601-2120  
PHONE (913) 625-5155 OPERATORS LICENSE NO. 9860

Date Well Completed 12/20/96  
Plugging Commenced 7:00AM 12/20/96  
Plugging Completed 9:30AM 12/20/96

Character of Well D&A  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)  
The plugging proposal was approved on 12/18/96 (date)  
by Marvin Miller (KCC District Agent's Name).

JAN 30 1997

01-30-97  
CONSERVATION DIVISION  
Wichita, Kansas

Is ACO-1 filed? Yes If not, Is well log attached? Yes  
Producing Formation None Depth to Top \_\_\_\_\_ Bottom T.D. 4130

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	217	8 5/8	216.83	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
1st Plug @ 1775' w/25sks 10sks In Mouse Hole Circulated 1st Plug 15 Minutes with 52 Vis. Mud  
2nd Plug @ 945' w/100sks 15sks In Rat Hole Plugs displaced with Mud.  
3rd Plug @ 270' w/40sks 200sks Total 60/40Poz 6%Gel w/1/2#FS/sk By Allied Cementing  
4th Plug @ 40' w/10sks Completed @ 9:30AM 12/20/96  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Discovery Drilling, Inc. License No. 31548  
Address P.O. Box 763 Hays, Kansas 67601

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Castle Resources, Inc.  
STATE OF Kansas COUNTY OF Ellis, ss.

Jerry Green

(Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed therewith are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) 1200 E. 27th, Suite C  
Hays, KS 67601

SUBSCRIBED AND SWORN TO before me this 21st day of January, 1996

Katherine Bray  
Notary Public



My Commission Expires: 6-19-2000



# Discovery Drilling

P.O. Box 763 • Hays, KS 67601 • OFFICE (913) 623-2920 • CELLULAR (913) 635-1511

15-195-22185-00-00

## DRILLER'S LOG

Operator: **CASTLE RESOURCES, INC.**  
1200 East 27th, #C  
Hays, KS 67601

Contractor: **DISCOVERY DRILLING, INC.**  
P.O. Box 763  
Hays, KS 67601

Lease: Bongarts "A" #1

Location: C/NW/SE  
Sec. 30/13S/21W  
Ellis Co., KS

Loggers Total Depth: 4130'

Rotary Total Depth: 4130'

Commenced: 12/13/96

Casing: 8 5/8 @ 216.83 w/135 sks

Elevation: 2336' Gr/2344'KB

Completed: 12/20/96

Status: D & A

## DEPTHS & FORMATIONS

(All measurements from K.B.)

Surface, Sand & Shales	0'	Shales	1798'
Dakota Sand	614'	Shales & Lime	2048'
Shales	801'	Shales	2132'
Cedar Hill Sand	1224'	Shales & Lime	2354'
Red Bed Shale	1497'	Lime & Shales	3559'
Anhydrite	1752'	RTD	4130'
Base Anhydrite	1798'		

STATE OF KANSAS )  
                          ) ss  
COUNTY OF ELLIS )

Thomas H. Alm of Discovery Drilling, Inc. states that to the best of his knowledge the above and foregoing is a true and correct log of the above captioned well.

Thomas H. Alm

Subscribed and sworn to before me on December 28 1996

My Commission Expires: 09-20-2000

Notary Public

