

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas


15-195-19051-00-00
32 13S 21W

Trego

County. Sec. Twp. Rge. (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW-SE-SW
Lease Owner The Superior Oil Company
Lease Name Pinney Well No. 38-32
Office Address Box 690, Chickasha, Oklahoma
Character of Well (completed as Oil, Gas or Dry Ho) Dry hole
Date well completed March 31, 1954
Application for plugging filed March 31, 1954
Application for plugging approved March 31, 1954
Plugging commenced March 31, 1954
Plugging completed March 31, 1954
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19...
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well E. R. Petty, Hays, Kansas
Producing formation None Depth to top Bottom Total Depth of Well 4109 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Penn Sd.	Water	4080	4084	10-3/4 7"	244 4109	None 3288

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Put in bottom plug. Filled with sand to 4040 ft. w/ 5 sacks cement on top of sand. Set plug at 248 ft. Put in 20 gals rock and 20 sacks cement. Set plug at 35 ft. Filled with 25 ft cement plug.

REV'D 04-05-54

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to The Superior Oil Company
Address Box 690
Chickasha, Oklahoma

STATE OF Oklahoma, COUNTY OF Grady, ss.
J. K. Lawson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) J. K. Lawson
Box 690, Chickasha, Oklahoma (Address)

SUBSCRIBED AND SWORN to before me this 6th day of April, 19 54
July 15, 1957
L. P. Stephens Notary Public.

PLUGGING
FILE NO. 32413-21W
BOOK PAGE 24 LINE 22

DRILLER'S LOG

15-195-19051-00-00

Company: The Superior Oil Co.
Farm: Pinney Well No: 38-32
Total Depth: 4109'
Comm: 2-25-54 Comp: 3-16-54
Contractor: Peel Brothers, Inc.

SW-SE-SW
Sec. 32, Twn. 13, Rge. 21
County: Trego, Kansas
Elevation:

Casing: 103/4" @ 244' Cem.
7 " @ 4109' Cem.

Production:

Figures below indicate bottom of formation

Clay and soil	0'	140'
Clay and shale		245
Shale		370
Blue shale		550
Shale, shells and sand streaks		615
Sand		700
Shale and shells		930
Shale		1050
Sand streaks		1390
Sand and shale streaks		1600
Shale		1668
Redbed and shale		1695
Anhydrite		1895
Redbed, shale and Anhydrite streaks		2255
Shale, lime and shells		2605
Shale and lime		2685
Brown lime		2720
Shale and lime		3240
Lime		3335
Lime and shale		3415
Lime and shale streaks		3485
Lime and shale		3625
Lime		3665
Lime and chert		3720
Lime		3800
Lime and chert		3820
Lime		3913
Lime and shale streaks		4005
Lime		4015
Lime and shale		4043
Lime		4048
Broken lime and sand		4056
Shale		4068
Lime		4081
Sand		4085
Conglomerate sand		4109
Total Depth		4109

This is to certify that the above information is to the best of my knowledge true and correct.

PEEL BROTHERS, INC.

BY Thurmond E. Peel

SUBSCRIBED AND SWORN TO before me this 19 day of March 1954

My commission expires September 28, 1957 Thomas S. Reese
Notary Public

PLUGGING
WELI SEC 32 T 13 R 21 W
BOOK PAGE 24 LINE 27