

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-195-22,087-00-00

LEASE NAME SCHUSTER

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER NO. 1

2970 Ft. from S Section Line

2210 Ft. from E Section Line

SEC. 32 TWP. 13S RGE. 21W (X) or (W)

COUNTY ELLIS

Date Well Completed 6-3-91

Plugging Commenced 7-16-91

Plugging Completed 7-18-91

LEASE OPERATOR AL-LA-LYN OIL, INC.

ADDRESS 614 W. 10th ST.

PHONE# 013, 726-3545 OPERATORS LICENSE NO. 7973

Character of Well GOOD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-25-91 (date)

by DENNIS HAMEL (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation CONGLOMERATE Depth to Top 4051 Bottom 4060' T.D. 4060'

Show depth and thickness of all water, oil and gas formations. ANHY TOP- 1660'

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION

Formation	Content	From	To	Size	Put in	Pulled out
SAND- SHALE	FRESH WTR	SURF	213	8 5/8"	213'	ZERO
SHALE-LIME-SAND	SALT WTR-OIL	SURF	4052	4 1/2"	4051'	3197'

III 31 1991
07-31-91

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. 7-16, Dumped 8 Sk Sd. 7-17, ELI dumped 4Sk of cement, 3970. 7-18-91, ELI shot csg off at 3197', pulled csg free, spotted 5 gel, 25 cmt, 21 gel. pulled to 1730', 25 Sk cmt, 22 bbl rotary mud, pulled to 875', 100 Sks cmt/250# hulls, 4 bbl water, at 265', 45sks cmt, to surf, lay out and fill cellar. Used 195 sk 60/40 10% gel.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor ALLIED CEMENTING CO, INC. License No. _____

Address P.O. BOX 31 RUSSELL, KS. 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: RICHARD ROMINE


STATE OF KANSAS COUNTY OF ELLIS, ss.

ROBERT A. WAHLMEIER (CONSULTANT) (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Robert A. Wahlmeier

(Address) 2213 VIRGINIA DRIVE, HAYS, KS.

67601



SUBSCRIBED AND SWORN TO before me this 22 day of July, 1991

Wilfred Kreuzer
Notary Public

My Commission Expires: July 31-1994