

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-195-20972-00-00

SE - SW
NE

, Sec. 36, T 13 S, R 21 W/E

feet from N/S section line

TECHNICIAN'S PLUGGING REPORT

feet from W/E section line

Operator License # _____

Lease Name HROEGER Well # 1

Operator: ZENITH PETROLEUM CORP.
Name &
Address BOX N.

County TREGO

GREAT BEND, KANS.
67530

Well Total Depth 4192 feet

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8 feet 339'

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON CEMENT CO. License Number _____

Address 1100 EAST 8TH ST. HAYS, KANS. 67601

Company to plug at: Hour: 11:30 AM Day: 19TH Month: OCT Year: 1982

VERBAL PLUGGING ORDERS GIVEN TO H. D. BELT

(company name) ZENITH PETROLEUM CORP. (phone) 316-792-1287

were: 8 5/8" - 339' EL - 1/200ST CMT. → 5 1/2" ESG. SET @ 4191' EL - 1/150ST CMT.

D.V. TOOL SET @ 1642' EL - 1/325ST CMT. - PLUG BACK. 3800' EL PERFS TOP. 3619'

ORDER 170ST 50% Pozmix 4% GEL - 3% CA-CL. → 21ST GEL - 4ST HULL'S.

AND 5 1/2" PLUG. - PUMP IN WITH PUMP TRUCK. → IN ANNULUS. 20ST CMT.

IN 5 1/2" - 10ST CMT. → 3ST HULL'S. → 40ST CMT. → 13ST GEL. → 1/2ST HULL'S. → 20ST CMT.

8ST GEL - REL - PLUG. AND 80ST CMT. Signed M. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:20 PM Day: 20TH Month: OCT. Year: 1982

ACTUAL PLUGGING REPORT 8 5/8" - 339' EL SB. CMC 1/200ST → 5 1/2" SET @ 4191' - 1/150ST CMT.

ORDERED - 170ST 50% Pozmix 4% GEL - 3% CA-CL. → 21ST GEL → 4ST HULL'S

AND 5 1/2" PLUG → PUMPED IN WITH PUMP TRUCK. IN ANNULUS 7 5/2"

PUMPED IN ANNULUS. 120ST CMT. AND - 3ST HULL'S - MAX. PRESSURE - 400^{PSE}

DUMPED IN 5 1/2" ESG. - 10ST CMT. - 3ST HULL'S. → 40ST CMT. → 13ST GEL.

1/2ST HULL'S. → 20ST CMT. → 8ST GEL. - RELEASE PLUG. NO PRESSURE.

Remarks: WE CHECKED FOR ADDITIONAL CEMENT 300ST 50% Poz-4-3

AND PUMPED AN ADDITIONAL 100ST CMT IN ANNULUS AS LISTED ABOVE.

AND AN ADDITIONAL 80ST AND 2ST HULL'S IN 5 1/2" ESG. MAX PRESSURE

250^{PSE} (CEMENTED BY HALLIBURTON)

I hereby certify that the above plugging instructions were given as herein stated

and that I (did) (did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

OCT 26 1982

CONSERVATION DIVISION
Wichita, Kansas

Signed M. Schmidt
(TECHNICIAN)

FORM CP-2/3
Rev. 9-82

INVOICE

11-5-82

1513-4