

6090179

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-195-21,607-00-00
NW 1/4 SEC. 31, T. 13 S., R. 21 W.
3300 feet from MS section line
4620 feet from N/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5342

Lease Name Borghardt Well # 1-31

Operator Name & Address Reason Exploration

County Trego

Address 410 17th St. Ste. 2300

Well Total Depth 4175 135.69 feet

Denver, Colorado
RECEIVED
STATE CORPORATION COMMISSION

Conductor Pipe: Size - feet -

Surface Casing: Size 8 5/8 feet 209

Abandoned Oil Well NOV 06 1984 Gas Well 11-06-84 Input Well SMD Well D&A

Other well as hereinafter CONSERVATION DIVISION Wichita, Kansas

Plugging Contractor Murphy Drilling Co. License Number 6033

Address 617 Union Center Bldg. Wichita, Ks. 67202

Company to plug at: Hour: Day: 13 Month: October Year: 19 84

Plugging proposal received from Mort Shupick

(company name) Murphy Drilling Co. (phone) 316-267-3241

were: Order 180 sks. 50/50 permit, 6% gel, 3% Cal. Cl. + 8 5/8" wire plug, spot all plugs w/ drill pipe w/ heavy mud between all plugs.

Plugging Proposal Received by Edwin A. Schumacher
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:00 AM Day: 14 Month: October Year: 19 84

ACTUAL PLUGGING REPORT 1st plug 1720' w/ 20 sks.
2nd plug 910' w/ 100 sks. + 1 sk. Cells-Flake
3rd plug 260' w/ 40 sks.
4th plug 40' solid bridge 1 sk. hulls + 10 sks.
10 sks in rat hole

Remarks: Clayton - 2307; Anhydrite - 1717; Anhydrite - no
(If additional description is necessary, use BACK of this form.) (Dowell)

I (did / did not) observe this plugging.

DATE 11-6-84

Signed Edwin A. Schumacher
(TECHNICIAN)

ENV. NO. 4635

10-14 NOV 19 1984

11-2-84
2