

6 070151

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 195-21,509 - 60-00
W 1/2 NE NW SEC. 30, T 13 S, R 21 W

1980 feet from N/EX section line
1650 feet from W/EX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Petty Well # E-2

Operator: Pickrell Drilling Company

County Trego

Name & Address 110 N. Market Suite 205

Well Total Depth 4151 134.91 feet

Wichita, Ks. 67202

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company License Number 5123 Tag 27

Address 110 N. Market Suite 205, Wichita, Ks. 67202

Company to plug at: Hour: 4 PM Day: 16 Month: May Year: 19 84

Plugging proposal received from Jerry Christopher

(company name) Pickrell Drilling Company (phone) (316) 262-8427

were: 8 5/8" 266' SP CUC w/200 sks 60/40 pozmix 2% gel 3% cal. cl. By Allied Cementing Co.

Order 220 sks 50/50 pozmix 6% gel 3% cal. cl.-1 sk cello flake and 8 5/8" plug.

Spot with drill stem, turn hole over, heavy mud between all plugs, no circulation problems,

Arbuckles @ 4125' Elevation 2346', Anhy 1765'

Plugging Proposal Received by Murray Schmitt
DOIC (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 7 PM Day: 16 Month: May Year: 19 84

ACTUAL PLUGGING REPORT Cemented by: Allied Cementing Company

1st plug @ 4110 w/25 sks cmt

2nd plug @ 1770 w/25 sks cmt

3rd plug @ 930 w/100 sks cmt w/1 sk cello flake

4th plug @ 270' w/50 sks cmt

5th plug solid bridge hulls plug @ 40 w/10 sks cmt

Remarks: 10 sks in Rat Hole (Circulation)

(if additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

DATE 5-22-84

Signed Murray Schmitt
DOIC (TECHNICIAN)

INV. NO. 1421

5-16

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1984
CONSERVATION DIVISION
Wichita, Kansas