

4-050261

12-20

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-195-22,185-00-00

C NW SE /4 SEC. 30, 13 S, 21 W
1980 feet from S section line
1980 feet from E section line

Operator license# 9860

Lease: Bongartz Well # A-1

Operator: Castle Resources, Inc.

County: Trego 134.22

Address: 1200 E. 27th Street - Suite C
Hays, Kansas 67601
913-625-5155

Well total depth 4130 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 217 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Discovery Drilling, Inc. License# 31548

Address:

Company to plug at: Hour: A.M. Day: 20 Month: December Year: 1996

Plugging proposal received from: Tom Alm

Company: Phone:

Were: Order 200 sxs 60/40 pozmix - 6% gel - 1/4# Flo-seal per sack.
Anhydrite 1752' - 1798'. Dakota 644' - 944'.

Plugging Proposal Received by: Marvin Miller 01-06-97

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour 9:30A.M., Day: 20, Month: December, Year: 1996

Actual plugging report:

- 1st. Plug at 1775' with 25 sxs cement.
- 2nd. Plug at 945' with 100 sxs cement.
- 3rd. Plug at 270' with 40 sxs cement.
- 4th. Plug at 40' with 10 sxs cement - 8 5/8" wiper plug.
- 15 sxs cement in rathole.
- 10 sxs cement in mousehole.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING. Elevation: 2344 GL

I did [] / did not [X] observe the plugging. HO

Marvin Miller (agent)

Form CP-2/3

INVOICED
DATE JAN 08 1997
INV. NO 47280
12 20