

4 050024

2-15

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
.200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 195-22,041-00-06
NE NE NW, SEC. 32, T 13 S, R 21 W XX
4950 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565
Operator: National Cooperative Refinery Asso
Name & Address: 1775 Sherman St. Suite 3000
Denver, Colorado 80203
303-861-4883

Lease Name Bongartz Well # 1
County Trego 135.36
Well Total Depth 4165 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 354

Abandoned Oil Well Gas Well Input Well SWD Well D&A x
Other well as hereinafter indicated

Plugging Contractor Allen Drilling Co. License Number 5418
Address Box 1389 Great Bend, Ks. 67530

Company to plug at: Hour: Day: 15 Month: Feb Year: 19 90

Plugging proposal received from Craig Christopher
(company name) (phone)

were: Order 215 sks 60/40 poz 6% gel 2 sks f.c. and
8 5/8" wiper plug. Spot all plus thru drill pipe with heavy mud
between all plugs.

Plugging Proposal Received by
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 10:30AM Day: 15 Month: Feb Year: 19 90

ACTUAL PLUGGING REPORT
1st plug at 4051 w/25 sks
2nd plug at 1700' w/25 sks
3rd plug at 890' w/100 sks
4th plug at 405' w/40 sks
5th plug at 40' w/10 sks
15 sks in rathole

FEB 23 1990
02-23-90

Remarks: CONSERVATION DIVISION
AR 4051 Elevation 2285 Anhydrite 1681 - 1709
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-26-90

J.H.S.

Signed Marvin Miller
(TECHNICIAN)
Marvin Miller

INV. NO. 27568
2-15