

6-100431

4-11

487
L

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-195-22,084 00-00

SW SW SW /4 SEC. 33, 13 S, 21 W
330 feet from S section line
4050 feet from E section line

Operator license# 30347 Lease Schuster well # 1

Operator: Decab Company County Trego

Address: P.O. Box 609 Well total depth 4088 feet 132.86
Hays, Kansas 67601 Conductor Pipe: inch @ feet
Surface pipe 8 5/8 Inch @ 204 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Western Kansas Drilling License# 4083

Address: Hays, Kansas 67601

Company to plug at: Hour: ?? Day: Month: Year:

Plugging proposal received from: Jim Manly

Company: Western Kansas Drilling phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 4030 feet with 25 sacks Rat hole: 15 sacks
2nd plug @ 1650 feet " 25 " Mousehole: sacks
3rd plug @ 855 feet " 100 "
4th plug @ 250 feet " 40 "

5th plug @ 40 feet " wiper plug & 10 sx

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:45 pm, Day: 11, Month: April, Year: 1991

Actual plugging report: Hole reported plugged as above.

Order 215 sx 60/40 pozmix w/ 6% gel and 2 sx celloflake or flowcel.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Elevation: 2257 GL, Anhydrite depth: 1643 - 1676 feet

MAY 02 1991
05-02-91
CONSERVATION DIVISION
Wichita, Kansas

Did penetrate Arbuckle, cemented by Halliburton

I did not [X] observe the plugging. David K. Wann

DATE 5-9-91

David K. Wann P.I.R.T. II
(agent)

INV. NO. 31783

G.S.