

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 195-20,290- 00-01

NW-NE-NE, Sec. 12, T 13 S, R 22 W

_____ feet from N/S section line

_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7601

Lease Name ALVIN Well # 1 (OWNED)

Operator: MID-AMERICA MINERALS
Name & Address BOX 518
HAYS, KANS.
67601

County TREGO

Well Total Depth 1555 feet # 59.5

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well NA

Other well as hereinafter indicated WENT OUT OF HOLE @ 970 FE

Plugging Contractor EMPHASIS DRUG. License Number 8241

Address BOX 506 4^S HAYAS, RUSSELL, KANS. 67665

Company to plug at: Hour: 6:45 AM Day: 8th Month: APRIL Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO BOB ELOER

(company name) MID-AMERICA MINERALS (phone) 628-1115

were: 8 5/8" - 253^{FE} SP. CUL

WENT OUT OF HOLE @ 970^{FE} DRILLED TO 1555^{FE} AND ABANDONED WELL.
ORDER 190ST 50% Formix 6% GEL, 3% CA-CL AND 8 5/8" PLUG
SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
BUT WENT OUT OF HOLE @ 970^{FE} THEY DRILLED TO 1555 AND DECIDED
TO PLUG.

Signed Marion J. Smith
(TECHNICIAN) 8016

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 6:45 AM Day: 8th Month: APRIL Year: 19 83

ACTUAL PLUGGING REPORT ORDERED 190ST 50% Formix 6% GEL, 3% CA-CL AND 8 5/8" PLUG

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.
1ST PLUG @ 1530^{FE} 30ST CNT., 2ND PLUG @ 870^{FE} 100ST CNT.
3RD PLUG @ 270^{FE} 40ST CNT., 4TH PLUG SAND BRIDGE HULLS - PLUG @ 40^{FE} 110ST CNT.

10ST CNT. IN RAT HOLE, (CIRCULATE)
CEMENTED BY ALLIED CNT.

Remarks: REENTRY (OWNED) COULDN'T GET DOWN.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Marion J. Smith
(TECHNICIAN)
HEC 18016
STATE CORPORATION COMMISSION

FORM CP-2/3
Rev. 9-82

INVOICED

DATE 4-22-83

INV. NO. 4092-W

APR 18 1983

CONSERVATION DIVISION
Wichita, Kansas