

4 060134

11-4

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-195-22,061-00-00
C-SE/4, SEC. 34, T 13 S, R 21 W/E
1320 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5145

Lease Name Weber Well # 4

Operator: Dreiling Oil Inc.

County Trego 134,87

Name & Address Box 1000

Well Total Depth 4150 feet

Victoria, KS 67671

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 226

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Lloyd Drilling Co. License Number 3300

Address St. Peter, KS.

Company to plug at: Hour: 1:15PM Day: 4 Month: November Year: 19 90

Plugging proposal received from Ron Nelson

(company name) Dreiling Oil (phone) _____

were: Order 225 sxs, 60/40 pos 6% gel 1/4# floccel per sx.

Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by Herb Deines
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None XXXXXX

Operations Completed: Hour: 1:15PM Day: 4 Month: November Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 4060' with 25 sxs. Arbuckle 4070'

2nd plug at 1720' with 25 sxs. Anhydrite 1696-1742'

3rd plug at 930' with 100 sxs. Dakota 628-928'

4th plug at 280' with 40 sxs. Surface pipe to 226'

5th plug at 40' with 10 sxs. STATE CORPORATION COMMISSION

rathole with 15 sxs. mousehole with 10 sxs. NOV 21 1990
11-21-90

Remarks: B-J Titan Cementing
(If additional description is necessary, use BACK of this form) Wichita, Kansas

INVOICED

xxxxx (do not) observe this plugging.

DATE NOV 27 1990

INV. NO. 30034

Gibbs

Signed [Signature]
(TECHNICIAN)

Herb Deines