



15-195-20159-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

Rec. 06-09-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Walker of Reins & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Walters Drilling Company,

Complete Address: 400 Insurance Building, Wichita, Kansas.

Lease Name: Birch Well No. 1

Location: CSE-NW Sec. 2 Twp. 13 Rge. (E)(W) 22

County: Trego Total Depth 4175' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

248'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section C 672'.

Circulate hole with heavy mud. Pull DP to 900' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set bridge C 40' with 1 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent