



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date April 25, 1959, authorized the following plugging operations:

Operator's Full Name: The Kimbark Co

Complete Address: Box 1557 Denver Colo.

Lease Name: Kraeger Well No. 1

Location: S 2 E 7 E Sec. 36 Twp. 13 Rge. 21 (E) (W)

County: Nez Total Depth: 3990

Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: Dry Hole

Operator was instructed to plug well as follows:

~~Run pits circulate hole with heavy mud, set cementing plug at 600 ft~~
~~and displace 20 sack cement thru drill pipe, heavy mud to 200 ft.~~
~~set cementing plug, and displace 15 sack cement, heavy mud to 40ft.~~
~~set and tie cementing plug in place with wire use 1/2 sac dry hulls and~~
~~displace 10 sack, cementing to base of cellar.~~

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 6 1959
 05-06-1959
 CONSERVATION DIVISION
 Wichita, Kansas

Very truly yours,
 Gilbert P. Leiker
 Signed: Gilbert P. Leiker
 Conservation Division Agent