

State of Kansas



15-195-20247-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSIONJUN 4 1974
06-04-74
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling Co., has this
date requested permission to plug the following described well:Mr. Wasinger guarantees payment of the plugging fee.Operator's full Name: Rains & Williamson Oil Company, Incorporated,Complete Address: 435 Page Court, 220 W. Douglas, Wichita, Kansas.Lease Name: Flax Well No. 1Location: NW-SE-NE Sec. 30 Twp. 13 Rge. (E)(W) 21County: Trego Total Depth 4150' Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Wasinger was instructed to plug the well as follows:246'--8 5/8" Surface casing, cement circulated with 160 Sx.4149'--5 1/2" casing cemented on bottom with 125 Sx.Sand well back to 4120' and set 5 Sx. cement with dump bailer. Pull 5 1/2"
casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150 Cu. Ft.
cement, staged.

Very truly yours,

Conservation Division Agent