



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 22 1974
08-28-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bishop of R & W Drlg. has this

date requested permission to plug the following described well:

Mr. Bishop guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Co.

Complete Address: 812 Union Ctr Wichita, Ks.

Lease Name: Alvin Well No. 1

Location: NW NE NE Sec. 12 Twp. 13 Rge. (E)(W) 22

County: Trego Total Depth 4080' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Bishop was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 750' & displace

70 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo F. Massey
Conservation Division Agent