



15-051-23046-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Larry Newell of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Operator's Full Name: Graham Michaelis Corporation

Complete Address: P.O. Box 247, Wichita, Ks. 67201

Lease Name: Disney Well No. 3-18

Location: NE NE SE Sec. 18 Twp. 13 Rge. 19 (E) (W)

County: Ellis Total Depth: 3790'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A XXX

Other well as hereafter indicated: \_\_\_\_\_

Mr. Newell was instructed to plug the well as follows:

8 5/8"-375' S.P. cuc. w/200 sacks common 2% Gel.-3% Cal.Cl.

Ordered 140 sacks 50/50 posmix-4% Gel.-3% Cal.Cl. & 8 5/8" plug.

Spot w/drill stem w/heavy mud between all plugs.

1st plug @ 720' w/80 sacks cement

2nd plug @ 380' w/40 sacks cement

3rd plug-solid bridge of hulls & plug @ 40' w/10 sacks cement.

Circulate 10 sacks in rat hole.

Very truly yours,

[Signature]  
Conservation Division Agent

STATE RECEIVED  
AUG 02 1982  
8-2-82  
CONSERVATION DIVISION  
Wichita, Kansas