



15-009-21721-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Holley of Allen Drilling Co. has this date requested permission to plug the following described well:

Mr. Holley guarantees payment of the plugging fee.

Operator's full Name: Crude Producers, Inc.

Complete Address: Box 55 Russell, Kansas 67665

Lease Name: Redetzke Well No. 2

Location: NE NW SW Sec. 20 Twp. 16 Rge. 13 (EX(W) X)

County: Barton Total Depth 3407' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Holley was instructed to plug the well as follows:

Fill hole with mud and spot 50 sx cement at 480'.

Fill hole with mud and spot 25 sx cement at 240'.

Fill hole with mud to 40' and 1/2 sx hulls, plus

10 sx cement to bottom of celler.

2 sx cement in rat hole.

266' of 9 5/8" surface casing cement circ.

Very truly yours,

Drew Rankin
Conservation Division Agent

RECEIVED
STATE CORPORATION COMMISSION

OCT 25 1979

CONSERVATION DIVISION
Wichita, Kansas