



15:051-21526:00:00

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

STATE RECEIVED  
CONSERVATION DIVISION  
AUG 14 1978  
WICHITA, KANSAS

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, Kansas 67202

Dear Sir:

Mr. Peltier of Western Petro. has this date requested permission to plug the following described well:

Mr. Peltier guarantees payment of the plugging fee.

Operator's full Name: Def Oil Operations

Complete Address: Box 503, Hays, Ks.

Lease Name: Dreiling Well No. 1

Location: 190'S NE SE NE Sec. 28 Twp. 13 Rge. (E)(W) 17

County: Ellis Total Depth 3541' Oil Well       

Gas Well        Input Well        SWD Well        D & A XX Lost Hole       

Mr. Pelteir was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 500' thru drill  
pipe. Heavy mud to 150' set 25 sk cmt plug thru drill pipe. Heavy  
mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo Massey  
Conservation Division Agent